

Obiekt: Willa "Kossakówka", MOCAK									MKT Konstrukcje	
Treść: DETALE PODBICIA FUNDAMENTÓW										
18.06.2021		Specyfikacja do rysunku nr: K2							2 / 3	
ELEMENT	NR PRĘTA	SZKIC PRĘTA [cm]	Φ	Φ	DLUGOSC l [cm]	ILOSC "n"		" n x l " [mb]	CIĘŻAR [kg]	
			S235JR	B500SP		na 1 El.	na Σ El.		wg Φ	Σ
1	2	3	4	5	6	7	8	9	10	11
B3	7			12	175.0	-	47	82.3	73.0	159.6 Σ=
	12			12	144.9	-	47	68.1	60.5	
	30		8		92.0	-	72	66.2	26.1	
szt. 6 C1	5			12	179.9	29	174	313.0	277.9	664.7 Σ=
	14			12	130.0	29	174	226.2	200.8	
	19			10	100.0	12	72	72.0	44.4	
	22		8		460.0	4	24	110.4	43.6	
	30		8		92.0	45	270	248.4	98.0	
szt. 37 C2	10			12	160.0	186	6882	11011.2	9775.9	20763.0 Σ=
	15			12	130.0	186	6882	8946.6	7942.9	
	19			10	100.0	12	444	444.0	273.7	
	23		8		420.0	4	148	621.6	245.3	
	30		8		92.0	188	6956	6399.5	2525.1	
szt. 11 C3	11			12	150.0	36	396	594.0	527.4	1173.5 Σ=
	17			12	100.0	36	396	396.0	351.6	
	19			10	100.0	12	132	132.0	81.4	
	24		8		400.0	4	44	176.0	69.4	
	30		8		92.0	36	396	364.3	143.8	
D	1			12	275.0	-	5	13.8	12.2	32.3 Σ=
	6			12	175.0	-	5	8.8	7.8	
	20			10	70.0	-	11	7.7	4.7	
	21		8		480.0	-	4	19.2	7.6	

[illegible]